Removing 15″ steel pipes from the "Y" Tank main and carting them to C. J. F.

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		Rs.
	Labour:				
1	Earthwork excavation and refilling with consolidation, etc. in all soils	C.yd.	0 0 3	9,350	
2	Removing, cleaning 15″ steel pipes 18 feet long, specials, lead jointings, etc.*	Cwt.	0 2 6	8,000	
3	Carting the 15″ pipes from the work spot to C. J. F. average distance 10 miles including stacking as per instructions	Cwt per mile.	0 0 6	80,000	

*About 10 lead jointings shall be melted to separate the lead and weighed in the presence of the Executive Engineer or his authorised agent who will fix the average weight of lead per joint, according to this weight per joint the contractor shall return the removed lead to the stores in the form of bricks.

The contractor will be held responsible for all damages to pipes during the transit or at the time of removing, etc.

V. GANESHA IYER,
Executive Engineer.

BUILDINGS DIVISION, BANGALORE.

Notification dated 28th January 1938.

A number of sites admirably suited for business premises, bungalows and cottages have been formed on the grounds of the old Mental Hospital on the Kempe Gowda Road, Bangalore City, situated in the heart of the City and in the midst of business locality of the town and they will be sold by public auction on Saturday the 26th February 1938, between 8-30 A.M. and 11 A.M. Details of the sites can be had at the Office of the Executive Engineer, Buildings Division, on any working day between 3 P.M. and 5 P.M.

Intending bidders must first deposit Rs. 50 at the commencement of the bid. In the case of the successful bidder, it will be adjusted towards the bid value. In the case of unsuccessful bidders, the amount will be returned to them at the end of the sale the same day. The site or sites will be knocked down to the highest bidder who has to deposit immediately 50 per cent of the bid amount and the balance in three days time.

The site or sites sold will be handed over after full payment of the bid value.

The confirmation of the sale rests with the Government.

Abstract Notification dated the 4th February 1938.

The attention of the public is hereby invited to the detailed notification calling for tenders for constructing a Police Station at Ooparpet, Bangalore City, published in pages 186-187, Part VI of *Mysore Gazette*, dated 10th February 1938.

The last date for the receipt of the tender is 25th February 1938.

B. R. GARUDACHAR,
Executive Engineer.

KOLAR DIVISION.

Notification dated 10th February 1938.

1. Sealed tenders will be received at the Office of the Executive Engineer, Kolar Division, up to 12 NOON on 5th March 1938, for constructing a Grainage Building at Talaganara in Chintamani Taluk.

2. Tenders in the prescribed form obtainable from the Office of the Executive Engineer, Kolar Division, should be addressed to the Executive Engineer, Kolar Division, in a sealed cover and

superscribed as "Tender for construction of a Grainage building at Talagavara." The name of the tenderer should also be superscribed on the top of the cover.

3. Each tender must be accompanied by treasury chellan for an earnest money of Rs. 130 paid to the treasury to the credit of "17 (a) P. W. Deposit" against the account of the Executive Engineer, Kolar Division. The earnest money of the successful tenderer will be retained as security deposit for the due fulfilment of the contract. Such a deposit in cash will not carry any interest.

4. The tenders will be opened in the presence of such tenderers who wish to be present on 5th March 1938 at Kolar Division. The final acceptance of the tender will rest with the Executive Engineer who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any.

5. The name of the successful tenderer will be posted on the Notice Board in the Executive Engineer's Office in due course. Within eight days of the acceptance of the tender, the successful tenderer will be required to execute an agreement in the Departmental Schedule Contract Form for the due fulfilment of the contract, and for the execution of all items of work in accordance with the Bombay specifications (1931) and also furnish a security of Rs. 260.

6. Failure to comply with the condition 5 above or to agree to carry out the work in accordance with the specifications and agreements in force will entail forfeiture of the earnest money.

7. The earnest money of rejected tenders will be returned on submission of the receipt originally granted, along with an application to the Executive Engineer.

8. Copies of contract documents, schedules, and drawings may be seen at any time at the Executive Engineer's Office, Kolar Division, on all working days between 11 A.M. and 5 P.M.

9. Specific rates should be given for each item in the schedule accompanying the tender and the rates should be in rupees, annas and pies and expressed in words and figures. Tenders offering a percentage reduction on the estimate amount will be rejected.

10. Any rates or lumpsum amounts for the items not called for, if tendered by the tenderer, will not be taken notice of. The rates for such items may be entered in a separate schedule with date and reasons for the same.

11. No alterations which are made by the tenderers in the tender form in the nomenclature of the items of work will be recognised and if corrections are made, the tenders are liable to rejection.

12. There should be no alterations or erasures in the tenders in the rates of items and any corrections made in the rates should be attested to and the number of corrections, if any, in each page noted at the foot of the same by the tenderer.

13. No reference should be made to the Public Works Department schedule of rates.

14. In the event of the tender being submitted by a firm, it must be signed separately and severally by each member thereof or in the event of absence of any partner, it must be signed on his behalf by a person holding power-of-attorney authorising him to do so.

15. When once the rates tendered have been accepted, they will not be revised under any circumstances. In regard to items of work not tendered, the rates for the same will be calculated by the Executive Engineer on the basis of current rates for materials and labour with a contractor's profit of 5 per cent as may be approved by the Superintending Engineer. This shall be final and legally binding on the tenderer.

16. The quantities given in the schedule are only approximate and the drawings shown to the contractor are only tentative and are liable to alterations, omissions, deductions or additions, at the discretion of the Executive Engineer or his representative. The tendered rates will hold good for any quantity, whether higher or lower than those given in the enclosed schedule.

17. The work should be completed and handed over in a tidy condition to the Public Works Department by the end of August 1938, failing which the Executive Engineer may, at his discretion, levy a penalty of Rs. 5 per day, which will ordinarily be calculated at 12 per cent per annum on the total outlay as liquidated damages for non-fulfilment of contract, and will be recovered from the contractor's outstandings for the period exceeded by him beyond the time fixed and until the work is completed and handed over.

18. In all matters of disputes of any kind not specially provided for in the agreement or of rates, penalties, measurements, quality of work, etc., the decision of the Chief or the Superintending Engineer shall be final and legally binding.

19. No claim for damages for delays caused by officers of the department in the execution of the work will be considered, whatever may be the reasons for such delays. The contractors should bear this in mind when tendering for the work. Extension of time due to delays caused by the departmental officers will, however, be considered on the merits of each case.

20. The contract should not be sublet.

21. All materials, tools and plant and machinery that will be supplied by the Executive Engineer in the interest of the work shall be accepted by the tenderer at the rates fixed by the Executive Engineer. The tenderer will pay the hire on tools and plant and machinery as per rules from the date of taking over of such machinery, tools and plant from the Stores to the date of return thereto, the dates considered being the dates of acknowledgments of the vouchers in each transaction.

22. The contractor should arrange for the payment of royalty and tolls.

Note.—(*a*) The contractor should at his own cost—

(1) Provide rods, stakes, ropes and labour required in setting out the work.
(2) Provide all necessary scaffolding, centering labour and appliances for hoisting.
(3) Provide motor mills, and sheds, to keep materials under cover and also for workmen.
(4) Arrange for protecting work during inclement weather.
(5) Supply requisite temporary lights, water cisterns, water pumps and hoses, sieves, parahs, shoring, strutting and other requisite protective appliances during the progress of the work.
(6) Supply all water required for work and workmen and shall provide temporary latrines and drains.
(7) Clean away all dirt, rubbish, superfluous materials and debris as they accumulate.
(8) Provide arrangements for pumping and baling of water from excavations and foundations, wherever and whenever necessary with his own pumping apparatus including necessary leading drains, slump pits, etc.
(9) Afford facilities to any other parties employed upon the work by the Public Works Department, so that their work may proceed during the progress of the contract, and give such persons the use of ordinary scaffolding and ladders.
(10) The contractor is responsible for all accidents to workmen, etc., on the work, and he must take precaution against all risk of accidents and, if necessary, provide for the same by insurance at the proper time.

Note.—(*b*) It is the business of the contractor to make his own arrangements for quarries and supplies of materials.

Abstract estimate for constructing a Grainage House at Thalagavara in Chintamani Taluk.

No	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		Rs.
1	Earthwork excavating foundation and filling in basement including watering and tamping, etc., complete	C.yds.	0 5 0	55	
2	Stone jelly concrete in ordinary mortar	C.ft.	0 3 0	521	
3	Size stone in mortar foundation	C.ft.	0 4 6	1091	
4	Burnt stone slabs 6″ thick one line dressed in exposed parts and fixed, etc., complete	Sq.ft.	0 5 0	366	
5	Burnt Brick in clay supeistructure	C.ft.	0 3 0	1135	
6	Burnt Brick in chunnam mortar as per deductions	C.ft.	0 4 6	292	
7	Burnt Brick in mortar archwork	C.ft.	0 5 9	21	
8	Teakwood door with 1½″ plank shutter, etc., complete including fitting	S.ft.	1 2 0	68¼	
9	Spring shutters to doors inside with wire gauge small mesh, etc., complete	S.ft.	1 0 0	68¼	
10	Teakwood windows half panelled and half glazed of shutters with cross flat iron bars and round iron bar of verticals of ¾″ dia. fitting, etc., complete	S.ft.	1 8 0	157½	
11	Fret work circular windows including fixing	S.ft.	1 8 0	3½	
12	Teakwood wrought and put up including all iron fittings and wood oiling, etc., complete	C.ft.	5 0 0	62·39	
13	King Rod Truses, etc., complete	No.	55 0 0	2	
14	Roofing with 1st class Mangalore Tiles (Yelahanka Tiles on 2″×½″ Teak Reepers, including wood oiling and tieing the bottom course tiles with wires and fittings on top with Teak Reepers, etc., complete	Sqr.	28 0 0	13·32	
15	Flooring with cement concrete 1 : 2 : 4 with cement rendering over 3″ stone jelly concrete with lime mortar, etc., complete	Sqr.	25 0 0	6·78	
16	Ridge Tiles set in mortar and painting with cement	R.ft.	0 7 0	37	
17	Plastering with chunnam mortar inside rooms alround	Sqr.	3 0 0	30·71	
18	White-washing 2 coats, including scaffolding as per above	Sqr.	0 4 0	30·71	

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		Rs.
19	Burnt brick in chunnam mortar, plastering with mortar building wall over roof, at ends ..	R.ft.	0 3 0	64	
20	Cement painting to basement alround	Sqr.	3 0 0	2·41	
21	Teakwood eave-boards plain 9″×$\frac{3}{4}$″ and fixing, etc., complete	R.ft.	0 7 0	146	
22	Teakwood turned finials and fixing, etc., complete	No.	3 0 0	2	
23	Teakwood pendents and fixing etc., complete ..	No.	1 0 0	4	
24	Chocolate painting including scaffolding charges.	Sqr.	3 0 0	7·64	
25	Clearing site and levelling the ground, etc., complete	Lumpsum Rupees.			

R. TIPPAIYA,
Executive Engineer.

MYSORE DIVISION.

Notification dated 7th February 1938.

It is hereby notified that the 1st Class Travellers' Bungalow at Hunsur will be closed for the public on Tuesday the 22nd February 1938 on account of Dewan's tour.

B. KRISHNA RAO,
Executive Engineer.

OFFICE OF THE ASSISTANT ENGINEER, HEADQUARTER RANGE, MYSORE.

Abstract Notification dated 26th January 1938.

The attention of the public is invited to the Notification published in Part VI, pages 152-158 of the *Mysore Gazette*, dated the 3rd February 1938, calling for sealed tenders for 'Construction of Pathological Institute in the premises of Krishnarajendra Hospital, Mysore.'

The last date for receiving tender is 21st February 1938. Earnest money to be deposited with the tender is Rs. 1,450.

Abstract Notification dated the 5th February 1938.

The attention of the public is invited to the Notification published in pages 193-198, Part VI of the *Mysore Gazette*, dated 10th February 1938, calling for sealed tenders for the construction of Anatomy Block on the western side of the Medical College, Mysore.

The earnest money to be deposited along with the tender is Rs. 1,700.

The last date of receiving tenders in sealed covers is 18th February 1938 before 3 P.M.

Abstract Notification dated the 5th February 1938.

The attention of the public is invited to the Notification published in pages 198-202, Part VI of the *Mysore Gazette*, dated the 10th February 1938, calling for sealed tenders for the construction of Krishnarajendra Police Station at Mysore.

The earnest money to be deposited along with the tender is Rs. 380.

The last date for receiving tenders is 26th February 1938, before 3 P.M.

Notification dated 10th February 1938.

1. Sealed tenders will be received at the office of the Assistant Engineer, Headquarter Range, Mysore, upto 3 P.M. on 25th February 1938, for constructing European special ward in Krishnarajendra Hospital, Mysore.